

BILL OF QUANTITIES

Item		Qty.	Unit	Unit Price	Total
A PRELIMINARIES AND GENERAL ITEMS					
1	Setting up of plant nursery including maintenance	1	LS		
PRELIMINARIES TOTAL					
B GROUND PREPARATION					
1	General site clearance including fine raking of the whole site to approval by the Horticulturalists	40,470	M ²		
2	Cut and fill to achieve recommended levels in all areas (bakfill)	1,218	M ³		
3	Ditto but with plant mix (this should include imported soil and manure where necessary)	1,218	M ³		
4	Allow for fumigation	40,470	M ²		
GROUND PREPARATION TOTAL					
C SOFT LANDSCAPE					
GROUNDCOVERS					
SCIENTIFIC NAME		COMMON NAME			
Supply, plant, weed, water and tend well the under-mentioned Assorted species of groundcovers till handing over					
1	<i>Bougainvillea glabra - creeper</i>	BOUGAINVILLEA	150	No	
2	<i>Cuphea ignea</i>	CUPHEA	200	No	
3	<i>Ficus pumila - creeper</i>	CLIMBING FIG	200	No	
4	<i>Helichrysum petiolare</i>	CURRY PLANT	200	No	
5	<i>Lantana selloum 'pink'</i>	PURPLE LANTANA	100	No	
6	<i>Lantana selloum 'white'</i>	WHITE LANTANA	100	No	
7	<i>Lantana selloum 'yellow'</i>	YELLOW LANTANA	100	No	
8	<i>Lavandula officinali</i>	LAVENDER	200	No	
9	<i>Liriope muscari 'grn. & var.' (20,35)</i>	MONKEY GRASS	300	No	
10	<i>Ophiopogon japonicum</i>	MONDO GRASS	500	No	
11	<i>Penisetum setaceum 'green'</i>	FOUNTAIN GRASS	25	No	
12	<i>Phormium tenax 'bronze'</i>	NEWZEALAND FLAX	200	No	
13	<i>Phormium tenax 'tricolor'</i>	VARIEGATED FLAX	200	No	
14	<i>Pyrostegia venusta - creeper</i>	GOLDEN SHOWER/ ORANGE	300	No	
15	<i>Russelia equisetiformis</i>	FIRECRACKER PLANT	300	No	
16	<i>Santolina chamaesaparissus</i>	COTTON LAVENDER	300	No	
17	<i>Thunbergia glandiflora -creeper/Campsis radicans</i>	THUNBERGIA/TRUMPET CREEPER	200	No	
GROUNDCOVER SUBTOTAL					

	INDOOR PLANTS				
	Supply the underlisted indoor plants to be used				
	by the Appointed Interior designer. Your rate				
	are for supply only unless otherwise advised by the				
	Interior Designer				
1	<i>Alocasia artopurpurea</i>	UPRIGHT ELEPHANT EARS	10	No	
2	<i>Alocasia macrorrhiza</i>	ELEPHANT'S EAR	10	No	
3	<i>Anthurium andraeanum</i>	FLAMINGO FLOWER	30	No	
4	<i>Asparagus densiflorus 'Sprengeri'</i>	SPRENGER'S FERN	20	No	
5	<i>Clivia miniata</i>	BUSH LILY	30	No	
6	<i>Dieffenbachia amoena</i>	DUMBCANE	35	No	
7	<i>Monstera deiciosa</i>	SPLIT- LEAF PHILODENDROM	30	No	
8	<i>Nephrolepis exaltata</i>	SWORD FERN	50	No	
9	<i>Santolina chamaecyparissus</i>	COTTON LAVENDER	40	No	
10	<i>Spathyphylum cochlearispathum</i>	PEACE LILY	40	No	
	INDOOR PLANTS SUBTOTAL				
	LAWN GRASS				
	Supply, plant to full establishment Buffalo				
	grass on all areas as instructed by the				
	L. Architect and Horticulturalist		6090	M ²	
	LAWN GRASS SUBTOTAL				
	SOFT LANDSCAPE TOTAL				
D	HARD LANDSCAPE				
1	Provide, place and position mazeras slates to be				
	used as walkways as instructed by the				
	Landscape Architect		300	M ²	
2	Garden features		13	No	
3	Outdoor Lighting		40	No	
4A	Automated Irrigation System				
a	63mm branch line		74	M	
b	50mm branch line		110	M	
c	40mm branch line		200	M	
d	20mm PPE Pipe		240	M	
4B	Sprinkler Heads				
a	Pop up pqp (Hunters)		4	No	
b	Pop up A 17 (Hunters)		4	No	
c	Pop up angle sprays (Hunters)		10	No	
4C	Control unit				
	4 station control unit		1	No	
4D	Pump and fittings				
	Solenoid valve		4	No	
	Gate valve		4	No	
	5HP Pump (Grnfos)		1	No	
	HARD LANDSCAPE TOTALS				

