

Kitchen Hood, Mechanical Ventilation, L.P. Gas Storage Tank and Distribution Services For The Proposed County

Assembly Block:

ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL (KSH.)
	<p><u>SPECIFICATIONS AND BILLS OF QUANTITIES FOR KITCHEN HOOD AND VENTILATION SYSTEM, L.P. GAS STORAGE TANK AND GAS DISTRIBUTION SERVICES TO THE PROPOSED CONSTRUCTION AND COMPLETION OF 1NO. OFFICE BLOCK FOR THE KILIFI COUNTY ASSEMBLY:</u></p> <p><u>ELEMENT NO.1:</u></p> <p><u>Kitchen Extract system:</u></p> <p><u>Extract System:</u> <u>Supply and fix the following Kitchen Extract System and associated Equipments:-</u></p>				
A	3.0X2.0 (20SWG) Stainless Steel Kitchen Hood	1	No.		
B	Grease Filter bank frame in stainless steel	1	ITEM		
C	450X450mm Duct from hood to fan manufactured from 20SWG galvanised mild steel sheet complete with 25x25mm G.M.S angle stiffeners	6	LM		
D	In Line Duct-mounted mixed flow roof extract fan duty 0.8m ³ /sec. against 100Pa static pressure	1	No.		
E	Flexible Connection	1	No.		
F	Fan Control Panel as described in the Particular Preliminaries	1	ITEM		
G	508x508mm grease filter panel ditto	1	ITEM		
H	Allow for Electrical works with this system	1	ITEM		
I	Allow for Testing and Commissioning	1	ITEM		

Kichen Hood, Mechanical Ventilation, L.P. Gas Storage Tank and Distribution Services For The Proposed County

Assembly Block:

TOTAL CARRIED TO COLLECTION PAGE (1)					
ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL (KSH.)
	<u>ELEMENT NO.2:</u>				
	<u>L.P.GAS INSTALLATION:</u>				
A	250gallon above ground Horizontal L.P.Gas Storage Tank (Size 2125 Long x 625mm Wide) complete with L.P.Gas, as 'Model Mobil' or other equal and approved. To complete with Filling valve, Magnetic float gauge, Multi-valve and 1st stage Automatic L.P.Gas Regulator all housed under a lockable-hinged cover, Safety Relieve Valve, Drain Plug, Main Isolating Valve Lifting Lung and Mounting feet, including all other necessary accessories for the proper functioning of the entire system and to approval	1	ITEM		
	<u>Copper Tubing (All Provisional)</u>				
B	15mm diameter heavy duty copper tubing installation as supply and distribution tubing	30	LM		
C	20mm diameter ditto	15	LM		-
D	25mm diameter ditto	15	LM		
	<u>Tees</u>				
E	10mm diameter heavy duty brass equal tee	4	No.		
F	15mm ditto	2	No.		
G	10x10x8mm diameter brass reducing tee	3	No.		
H	25x25x20mm ditto	1	No.		
	<u>Stop Cocks</u>				
I	10mm diameter Stop Cock	1	No.		
J	15mm ditto	1	No.		
K	20mm ditto	1	No.		
L	25mm ditto	1	No.		
	<u>Testing</u>				
M	Allow for Testing the whole L.P.Gas Installation both during progress and at Commissioning to the Engineer's satisfaction and to leave the it in sound and good working condition	1	ITEM		

Kichen Hood, Mechanical Ventilation, L.P. Gas Storage Tank and Distribution Services For The Proposed County

Assembly Block:

TOTAL CARRIED TO COLLECTION PAGE (2)					
ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL (KSH.)
	<p><u>ELEMENT NO.3:</u></p> <p><u>PROVISIONAL SUMS</u> <u>The following Provisional Sums to be measured on completion and priced in accordance with the rates contained in these Bills of Quantities or prorata thereto or deducted in whole if not required.</u></p>				
A	Provide a Provisional Sum of Kenya Shillings Fifty Thousand (Kshs. 50,000.00) only for Engineers Supervision and Contract Administration Expenses.	1	ITEM	50000	50,000.00
B	Provide a Provisional Sum of Kenya Shillings Two Hundred Thousand (Kshs.200,00.00) only for Contingencies	1	ITEM	200000	200,000.00

Kichen Hood, Mechanical Ventilation, L.P. Gas Storage Tank and Distribution Services For The Proposed County

Assembly Block:

	TOTAL PROVISIONAL SUMS CARRIED TO COLLECTION.....(3)				250,000.00
ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL (KSH.)
	<u>MAIN SUMMARY PAGE:</u>				
	PRELIMINARIES BROUGHT FORWARD FROM.....PG(G-6)	
	TOTALS BROUGHT FORWARD FROMPG(1)	
	TOTALS BROUGHT FORWARD FROMPG(2)	
	PROVISIONAL SUMS BROUGHT FORWARD FROM..PG(3)	250,000.00
	SUBTOTALS.....				
	ADD 16% V.A.T.....				
	GRAND TOTAL.....				
	AMOUNT OF TENDER SUM IN WORDS KENYA SHILLINGS.....				
	NAME ADDRESS OF THE CONTRACTOR.....				
	DATE.....SIGNATURE.....				
	NAME ADDRESS OF THE WITNESS.....				
	DATE.....SIGNATURE.....				

*Kichen Hood, Mechanical Ventilation, L.P. Gas Storage Tank and Distribution Services For The Proposed County
Assembly Block:*

--	--	--	--	--	--

ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL (KSH.)	
	<u>(SUMMARY OF COLLECTION)</u>					
	PRELIMINARIES B/F FROM PAGE G-6.....				1,000,000.00	
	CARRIED TO COLLECTION	PG (1)			#BEZUG!	
	" " "	" (2)			#BEZUG!	
	" " "	" (3)			#BEZUG!	
	" " "	" (4)			#BEZUG!	
	" " "	" (5)			#BEZUG!	
	" " "	" (6)			#BEZUG!	
	" " "	" (7)			#BEZUG!	
	" " "	" (8)			#BEZUG!	
	" " "	" (9)			#BEZUG!	
	" " "	" (10)			#BEZUG!	
	" " "	" (11)			#BEZUG!	
	" " "	" (12)			#BEZUG!	
	" " "	" (13)			#BEZUG!	
	PROVISIONAL SUMS				#BEZUG!	
	SUB-TOTAL				#BEZUG!	
	ADD 16% V.A.T					
	GRAND TOTAL COLLECTION TO FORM OF TENDER				#BEZUG!	
	TOTAL TENDER SUM IN WORDS					

NAME AND ADDRESS OF CONTRACTOR						
DATE:.....SIGNATURE						

NAME AND ADDRESS OF WITNESS						
DATE.....SIGNATURE						

