

INSTALLATION OF 1No. STANDBY DIESEL GENERATOR FOR COUNTY ASSEMBLY OFFICES MALINDI - KILIFI COUNTY

ITEM No.	DESCRIPTION	QTY	UNIT	RATE	SHS.
"A"	<p>Supply Install. Test and Commission Following:-</p> <p>Diesel Generator Model C220D5 enclosed set 220KVA standby, 200KVA Prime rated complete with residential exhaust silencer, Battery charger, QSB7 G5 Engine and Newage Stamford Alternator-complete with canopy and Amf panel, 4-pole Automatic changeover switch and 2No. Auxilliary Bypass switch including associated wiring in a lockable compartment</p>	1	No.		
TOTAL C/F TO PRICE SUMMARY PAGE					-
A	<p><u>PRICE SUMMERY PAGE</u></p> <p>TOTAL B/D FROM PAGE E/1</p>				

ITEM No.	DESCRIPTION	QTY	UNIT	RATE	SHS.
	SUB-TOTAL				
	ADD 16% VAT				
	GRAND TOTAL				

TOTAL TENDER SUM IN WORDS.....

NAME OF CONTRACTOR:

DATE: SIGNATURE:

OFFICIAL RUBBER STAMP:

PIN: V.A.T. REG. No.:

WITNESS NAME:

ADDRESS:

DATE:

INSTALLATION OF 1No. STANDBY DIESEL GENERATOR FOR COUNTY ASSEMBLY OFFICES MALINDI - KILIFI COUNTY

STANDBY GENERATOR SPECIFICATIONS

Generator Model	C220 D5e
Prime Power (kW)	200
Standby Power Generator (KVA)	220 Super silent
Rated Frequency (Hz)	50
Rated Speed (rpm)	1500
Engine Brand	Diesel Engine
Speed Governor type	Electronic
Cycle	Four Stroke
Fuel Consumption at 100% Load L/h	48.8 (Stby), 45.6 (Prime)
No. of Cylinder	6
Alternator Model	UC1274H
No. Bearing	1
Dimension approx.	3900mm x 11100mm x 2246mm
Weight	2698Kg (Dry), 3301Kg (Wet)
Noise	Super Silent Type
Bore,mm	107
Stroke,mm	124
Fuel flow, L/hr	106