



Notes

ALL WORK TO BE CARRIED OUT IN ACCORDANCE TO COUNCIL REGULATIONS.

FIGURED DIMENSIONS TO BE GIVEN PREFERENCE TO SCALED DIMENSIONS.

ALL WALLS BELOW 200MM TO BE HOOP IRONED AT EVERY ALTERNATE COURSE.

PROVIDE DAMP PROOF COURSE 200MM ABOVE GROUND LEVEL UNDER ALL NEW WALLS.

P.V. INDICATES PERMANENT VENTILATIONS.

ALL DRAINAGE UNDER THE BUILDING AND DRIVE TO BE ENCASED IN 200MM CONCRETE SURROUND.

ALL INSPECTION CHAMBERS ON DRIVEWAY TO BE OF HEAVY DUTY TYPE.

ALL DRAINAGE AND PLUMBING TO BE IN ACCORDANCE WITH M.C.H RULES AND REGULATIONS.

CONTRACTOR TO CHECK ALL DIMENSIONS ON SITE.

500G POLYTHENE SHEETING AND ANTI-TERMITE TREATMENT TO BE PROVIDED UNDER GROUND FLOOR SLAB.

ALL STRUCTURAL WORKS TO BE IN ACCORDANCE TO STRUCTURAL ENGINEERS DETAILS.

Office Block For County Assembly of Kilifi.

Plot no. 2146 Malindi.

Working Drawing
Gym, Toilet Block Details

Drg No. H. B. 2014.08.49

scale
As shown

Corbel Consultants
ARCHITECTS.
Harish V. Bhatt
B. Arch A.I.A. M.A.A.K (A1226)
P.O Box 87537, Tel +254722703215
Mombasa Kenya
Email: harrybhatt2@yahoo.com